

BANGALORE DIVISION.

Dated 1st February 1930.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., 17th February 1930, for constructing quarters for 2 Inspectors and 1 Assistant Superintendent on the premises of the Channarayana Silk Farm. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, shewing the rates at which the different items specified will be executed.

4. Tenders quoting percentages below or above estimate will not be received.

5. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing quarters for 2 Inspectors and 1 Assistant Superintendent on the premises of the Channarayana Silk Farm" in default of which, tenders will be rejected.

6. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

8. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

At direct quantities for constructing double block for Sericultural Inspectors at Channarayana.

No.	Items of work	Per	Quantity	Rate
1	Earthwork excavation and filling in basement	C.yd.	39	
2	Stone jelly in chunam concrete foundation	C.ft.	528	
3	Stone in clay foundation and basement	"	658	
4	Burnt brick in clay superstructure	"	2474	
5	Stone slabs 6" thick on dressed	S.ft.	75	
6	Stone slabs 6" thick roughly dressed including cutting dots for bressummer.	"	52	
7	Chunam plastering	Sqr.	1273	
8	Chunam pointing with thread lines	"	121	
9	White and colour washing two coats	"	1395	
10	Chunam patty or border	R.ft.	82	
11	Providing mortar and pestle	Each	2	
12	Constructing sinks, etc., complete	"	2	
13	Flooring with 3" stone jelly in lime concrete with chunam plasters on top.	Sqr.	504	
14	Flooring with Caddappa slabs on 3" lime concrete and cement pointed.	"	152	
15	Roofing with First Class Mangalore tiles on teakwood reapers 2" x 1" with cement pointing.	"	1260	
16	Ridge tiles set in mortar and cement pointed	R.ft.	30	
17	Ventilators tiles and cement pointed	Each	6	
18	Teakwood work wrought and put up with two coats of wood oiling.	C.ft.	3102	
19	Teakwood battened doors with 1 1/2" thick shutters with hinges, bolts and nuts, etc., complete.	S.ft.	182	
20	Teakwood windows with battened shutters 1" thick with iron bars 5/8" dia. hinges, etc., complete.	"	48	
21	Teakwood ventilators glazed	"	12	
22	Painting with three coats of chocolate paint	Sqr.	472	
23	Teakwood plank 1" thick for shutters fixed complete with wooden plugs.	S.ft.	18	

H. R. VENKATASUBBA RAO,
Executive Engineer.